

15.057.20417.00.00

Form CP-3
Rev. 6-26-62

KANSAS

14

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Woodman - Iannitti Drlg. Co.

Complete Address: 706 Union Center Bldg., Wichita, Kansas

Lease Name Madden Well No. 2

Location C S/2 NW SW Sec. 24 Twp. 12 Rge. (E) (W) 18

County Ellis Total Depth 3697'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 7P Day 16 Month 4 Year 1969

The Above well was plugged as follows:

RTD 3697' 8 5/8 csg set at 188' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk cmt.

thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base

of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing
Well Plugging Supervisor

DATE 4/21/69

INV. NO. 9643-u