

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
JAN 23 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil, Inc.

Complete Address R.R. # 2 Victoria, Kansas

Lease Name Schmidt Well No. 1

Location SE SW NW Sec. 34 Twp. 12 Rge. (E) (W) 17

County Ellis Total Depth 3633'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 12 N Day 21 Month 1 Year 1973

The above well was plugged as follows:

RTD 3633' 8 5/8 csg set at 205' cwc 150 sk. Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk
cmt thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sk cmt
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/24/73
INV. NO. 6899-W

Signed: Leo J. Wessing
Well Plugging Supervisor