

State of Kansas



15.159.20037.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1967
CONSERVATION DIVISION
Wichita, Kansas
May 12, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Sam Farmer of John O. Farmer, Inc. has this date requested permission to plug the following described well:

Mr. Farmer guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Inc.

Complete Address: 370 W. Wichita Dr., Russell, Kansas

Lease Name: Swartz Well No. 1

Location: NW NW SE Sec. 36 Twp. 21 Rge. 10 (E) (W) X

County Rice Total Depth 3615' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Farmer was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/4 sack hulls to 200' and
cement hole with 25 sacks through drill pipe. Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

William J. Loman
Conservation Division Agent