

15.051.30624.00.00

State of Kansas



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION  
(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

JAN 5 1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Crowe of Garvey Drlg. has this date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Inc.,

Complete Address: 500 West Douglas, Wichita, Ks.

Lease Name: Wasinger "F" Well No. 2

Location: SE NW NE Sec. 15 Twp. 11 Rge. 18 (E)(W) X

County: Ellis Total Depth 3125 ~~3190~~ Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Crowe was instructed to plug the well as follows:

Gun pitsm circulate hreavy mud, set cementing plug at 1050' and displace  
70 sc cement thru drill pipe. Heavy mud to 300' set cementing plug and  
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole  
with 2 sc cement.

Very truly yours,

Len J. Mosey  
Conservation Division Agent