

State of Kansas



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 CONSERVATION DIVISION
 WICHITA, KANSAS
 DEC 5 1967

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Oller of Murfin Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Oller guarantees payment of the plugging fee.

Operator's full Name: Red Oniom

Complete Address: Aspen Colorado

Lease Name: Kohl Well No. 1

Location: SW SE SE Sec. 25 Twp. 12 Rge. 20 (E) (W) X

County: Ellis Total Depth 3875 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Oller was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace
100 sc cement thru drill pipe. Heavy mud to 210' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole with
2 sc cement.

Very truly yours,

Ben F. Massey
 Conservation Division Agent