

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____
LOCATION NE NE SW
SEC. 27 TWP. 14 RGE. 16

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Rohleder 370 W. Wichita Ave

Operator Jones Shelburne-Farmer, Inc. Address Russell, Kans

Field _____ County Ellis

Total Depth 3370 Feet.

Plugging Contractor Same & Globe Cementing

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 950' circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at 500'
displaced 30 sax cement through drill pipe, heavy mud to 250', set
cementing plug and displaced 50 sax cement through drill pipe, heavy
mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement
to bottom cellar.

J. L. Letty

District Conservation Agent

Date 9-27-57

STATE CORPORATION COMMISSION

SEP 30 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 27 T. 14 R. 16W
BOOK 49 LINE 35