

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

RECEIVED
STATE CORPORATION COMMISSION
FORM CP-3
Rev. 6-4-68
AUG 21 1980
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 - - (OWWO) (of this well)

Operator's Full Name EAGLE OIL COMPANY

Complete Address NORTH MAIN ST. VICTORIA, KANS. 67671

Lease Name R. J. ROHLER (OWWO) Well No. #1

Location NE-NE-SW, Sec. 27 Twp. 14 Rge. 16 (W) (W)

County ELLIS Total Depth 3378 FT

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated _____

Plugging Contractor JAY-LAN - CORPORATION

Address 207 WEST 12TH ST. HAYS, MO License No. _____

Operation Completed: Hour 9:00 AM Day 19 Month JULY Year 1980

The Above well was plugged as follows:

8 5/8" 960 FT SP. CMC.
ORDERED 110 ST 50/50 PERMIX 6% GEL. + 8 5/8" PLUG.
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
1ST PLUG. @ 930 FT w/ 70ST CMT.
2ND PLUG. @ 330 FT w/ 25ST CMT
3RD PLUG. → SOLID BRIDGE HULL'S + PLUG. @ 40 FT / 10ST CMT.
5ST IN RAT HOLE

CEMENTED BY ALLIED CMT

I hereby certify that the above well was plugged as herein stated.

Lease Name
& Location Parent's Made 9-5-80
INV. NO. 30532

Signed: Maureen Schmidt
Well Plugging Supervisor

State of Kansas



15.051.01706.00.01

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

September 5, 1980

WELL PLUGGING AUTHORITY

R.J. Rohleder #1
NE NE SW, Sec.27-14S-16W
Ellis County
3378'
Jay-Lan Corporation


Eagle Oil Company
N. Main Street
Victoria, KS 67671

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) day from the above date.

Yours very truly,


J. LEWIS BROCK, Administrator

Mr. Marion Schmidt. 2104 Canterbury Rd., Hays, KS 67601

is hereby assigned to supervise the plugging of the above named well