

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 5 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Abercrombie Drg Co

Complete Address: 801 Union Center Wichita, Kansas

Lease Name Orth Well No. 1

Location NW SE SW Sec. 4 Twp. 14 Rge. (E) (W) 19

County Ellis Total Depth 3920

Abandoned Oil Well Gas Well Input Well SWD Well D & A x

Other well as hereafter indicated:

Plugging Contractor: Hellar Drg Co

Address: Wichita, Kansas License No.

Operation Completed: Hour 10AM Day 2 Month 12 Year 63

The Above well was plugged as follows:

8 5/8" 220' circulated with cement.

Circulated hole with heavy mud, set plug at 550', displaced 20 sax cement
through drill pipe, heavy mud to 180', set plug and displaced 20 sax
cement through drill pipe, heavy mud to 35', set plug, hulls and filled to
bottom cellar with cement.

I hereby certify that the above well was plugged as herein stated.

Signed: Edson Petty
Well Plugging Supervisor

INVOICED
DATE 12/5/63
INV. NO. 8229-11