

KANSAS

af
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Fender Pipe & Supply, Inc.

Complete Address: Box 302 Russell, Kansas 67665

Lease Name Engel "C" Well No. 2

Location SW SW NW Sec. 34 Twp. 14 Rge. 18 (E) (W) XX

County Ellis Total Depth 3674

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Russ Casing Pulling Company

Address: Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 2p Day 11 Month 9 Year 1968

The Above well was plugged as follows:

Total Depth 3674' 8 5/8 csg set at 231' cwc

5 1/2 csg set at 3660' cw 100 sc cement.

5 1/2 csg PBD 3660 with top perf at 3341'.

Set 5 1/2 plg at 3200', poured 30' sand (3170-3200) and dumped 5 sc cement with dump bailer.

Cutoff and recov. 2000' of 5 1/2 csg. (3130-3170)

Pumped thru 8 5/8 plg container with 25 sc gel W/500 lbs. hulls, plug and 130 sc

50-50 poz cement with 6% total gel. Max pres. 200 lbs. SI pres. 50 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: *Geo F. Massey*
Well Plugging Supervisor

INVOICED

DATE 9/13/68
INV. NO. 8456-w