

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION NW NW SWSEC. 33 TWP. 14 RGE. 18Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Engel _____Operator Tomlinson & Kathol Address 414 Union Center Wichita,Field _____ County EllisTotal Depth 3704 Feet.Plugging Contractor West Supply Co & ~~State~~ Sun Cementing CoPlugging Contractor's License No. 14

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 277' circulated with cement - 5 1/2" 3600', with 100 sax
cement behind - P. B. to 3342' perforated 3317'.

Filled with sand to 3300', set 4 sax cement with dump bailer,
pulled 3090' 5 1/2" to 1100', circulated hole with heavy mud at 1100',
40 sax Gel), pulled 5 1/2" to 500', displaced 35 sax cement through 5 1/2",
at 500', heavy mud to 265', displaced 25 sax cement through 5 1/2" at
165', heavy mud to 35', set rock and 10 sax cement to bottom cellar.

Mudding and Cementing by Sun Cementing Co.

E. L. Terry
District Conservation Agent

Date _____

9-11-57

STATE CONFIRMED
SEP 13 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC. 33 T. 14 R. 18WBOOK PAGE 45 LINE 19



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS

September 16, 1957

CORRECTED COPY


Well No.	1
Lease	Engel
Description	SW SW NW 33-14-18W
County	Ellis
File No.	45-19

Tomlinson & Kathol
1114 Union Center
Wichita, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

Very truly yours,


Jewel M. Ogden
Director of Conservation Division

cc:
District Plugging Supervisor