

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION NE NE SW

SEC. 28 TWP. 14 RGE. 17 W

Dry Hole x Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Peter *Box 239*  
*Route 12*

Operator Lion Oil Co Address ~~Wichita, Kans~~

Field \_\_\_\_\_ County Ellis

Total Depth 3500 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 1120' circulated with 550 sax cement - 5 1/2" at  
3491 with 150 sax cement behind.

Filled with chat to 3480' set 4 sax cement with dump bailer,  
pulled 2600' 5 1/2", filled with mud to 300', set rock bridge and  
20 sax cement, filled with mud to 40', set rock and 10 sax  
cement to bottom cellar.

STATE OF KANSAS

JAN 21 1952  
CONSERVATION DIVISION  
WICHITA, KANSAS

*J. Peter*  
District Conservation Agent

Date 1-17-52

PLUGGING  
FILE SEC 28 T 14 R 17 W  
BOOK PAGE 139 LINE 18

*[Handwritten signature]*