


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County. Sec. 36 Twp. 21 Rge. 13 (E) 13 (W)
Location as "NE/CNW/SW" or footage from lines E 1/2 / NE 1/2
Lease Owner Nadle and Gussman
Lease Name Fisher Well No. C 3
Office Address RFD #1, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 5-17-56 19
Plugging completed 5-23-56 19
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Brundege
Producing formation Depth to top Bottom Total Depth of Well 3732 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2853.36

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging started 5-17-56 and completed 5-23-56. Plugged off bottom with 155' of rock and dumped in 5 sacks of cement. Shot casing at 2844'. Circulated and spotted 80bbls. of oil. Filled hole with heavy mud. Set permanent rock bridge at 240' and dumped in 20 sacks of cement. Filled hole from 240' to 30' of top with heavy mud. Dumped in 10 sacks of cement for cap on well.

RECEIVED
STATE CORPORATION COMMISSION
MAY 25 1956
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor J. O. Forbes, d/b/a/ Forbes Casing Pulling
Address Box 221, Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
Box 221 Great Bend (Address)

SUBSCRIBED AND SWORN TO before me this 24 day of May, 19 56

My commission expires April 8, 1957

Arthur F. Zickel
Notary Public.

PLUGGING
FILE SEC. 36 T. 21 R. 13W
BOOK PAGE 56 LINE 27

WELL LOG

MADEL AND GUSSMAN

FISCHER C No. 3

C EL NE NE 36-21-13W
Stafford County, Kansas

Comm. 12-16-51
Comp. 12-28-51

Casing: 8-5/8" 342' w/225 sax
5-1/2" 3751' w/150 sax

Sand and shale	290
Red Bed and shale	342
Cement, sand, red bed and shells	402
Red bed and shale	702
Anhydrite	750
Red bed shale and shells	1035
Shale and shells	1320
Shale and silt	1465
Broken lime and shale	1695
Lime and shale	1800
Lime	1875
Shale and lime	2320
Shale and shells	2700
Shale and lime	3292
Lime	3364
Lime and shale	3408
Lime	3550
Lime and chert	3581
Conglomerate	3614
Shale and sand	3650
Lime	3690
Arbuckle Lime	3717
Arbuckle Dolomite	3732

GEOLOGICAL TOPS

Heebner	3170
Brown Lime	3296
Lansing-K.C.	3312
Viola	3562
Simpson withered Sh.	3597
Simpson (Green) Shale	3628
Arbuckle	3655

STATE OF KANSAS

COUNTY OF SEDGWICK

} SS:

L. C. Hay, of lawful age, states that the above depths and formations are correct as shown by the daily drilling log of the Fischer C No. 3 in the Center of the East Line NE NE 36-21-13W, Stafford County, Kans.

L. C. Hay

Subscribed and sworn to before me this 4th day of January, 1952.

Paul Bass

Notary Public

My commission expires Nov 22 1952

RECEIVED

APR 24 1956

REGISTRATION DIVISION
Kansas

PLUGGING
FILE SEC 36 T 21 R 13W
BOOK PAGE 56 LINE 27