

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.185.19546.0000

API NUMBER N/A

LEASE NAME Fischer

WELL NUMBER C-4

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 36 TWP. 21 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 2-18-92

Plugging Completed 2-21-92

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel & Gussman

ADDRESS 3200 First Natl Twr Tulsa, Ok. 74103

PHONE# (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, Is well log attached?

Producing Formation Depth to Top Bottom T.D. 3624'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	330'	none
				5 1/2"	3621'	2493'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Sanded bottom to 3570' ran 5 sacks cement. Shot pipe @2595', 2493'. Plugged with 3-hylls, 10 gel, 50 cement, 10 gel, 2 hulls, 125 sacks cement 60/40 6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Kelso Casing Pulling, Inc. RECEIVED

STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *R. Darrell Kelso*

(Address) P.O. Box 347 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 25 day of February, 19 92

Irene Herzberg
Notary Public

My Commission Expires:

IRENE HERZBERG
Notary Public
My Appt. Exp. Aug. 24, 1993

JAN 27 1992

WELL LOG

Nedel and Gussman

FISCHER C No. 4

CONSERVATION DIVISION
MICHOTA 468
NW NE NE 36-21-13W
Stafford County, Kansas

Comm: 2-24-52
Comp: 3-5-52

Casing: 8-5/8" @ 330' 300 sax
5-1/2" 3621' 150 sax

Formations	Depth
Sand, gravel and shale	270
Red rock, shale and shells	330
Red rock and shells	615
Red rock and shale	689
Anhydrite	721
Shale, shells and red bed	1290
Shale and shells	1570
Broken Lime	1625
Lime	1660
Lime and shale	1753
Broken Lime	1890
Shale and lime shells	2100
Shale and lime	2245
Shale and lime shells	2750
Shale and lime	2970
Lime	3085
Lime and shale	3212
Broken lime and shale	3324
Lime	3515
Lime and chert	3569
Shale	3584
Shale and sand	3620
Dolomite	3624

Geological Tops

Heebner	3148
Brown Lime	3276
Lansing-Kansas C.	3293
Viola	3532
Simpson Shale	3568
Arbuckle	3620

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

L. O. Hay, of lawful age, deposes and states that the above formations and depths are correct as shown by the daily drilling log of the Fischer C No. 4 located in the NW NE NE 36-21-13W, Stafford County, Kansas.

L. O. Hay

Subscribed and sworn to before me this 10th day of March, 1952.

Walter Barr
Notary Public

My commission expires Nov. 3, 1952