

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.185.13255.0000
API NUMBER N/A
LEASE NAME FISCHER
WELL NUMBER C-1
SPOT LOCATION NW NW NE
SEC. 36 TWP. 21 SRGE. 13 (●) or (W)
COUNTY Stafford
Date Well Completed 10-31-48

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3232 First National Tower - Tulsa, OK 74103

PHONE # (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Commenced 10-14-87
Plugging Completed 10-14-87

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1 - Dodge City

Is ACO-1 filled? N/A If not, is well log attached? Yes

Producing formation Lansing-K.C. Depth to top 3634' bottom 3636' T.D. 3636'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Oil	3634	3636	8-5/8"	320'	None
				5-1/2"	3634	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Mixed 150 sacks ATL cement with 500# hulls, pumped down 5-1/2" casing @ 500# Max. press. and 200# SIP. Mixed 150 sacks with 200# hulls, pumped down 8-5/8" - Max press. 500# and 300# SIP - Total cement used 300 sacks.

Witnessed by state plugger, Duane Rankin

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Company License No. None required

Address Box 31 - Russell, Kansas 67665

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

M. R. Taylor, Manager of Production (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

OCT 22 1987

(Signature) M R Taylor
3232 First National Tower
(Address) Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 20th day of Oct., 1987

My Commission expires: May 11, 1991

Mildred Carter
Notary Public

RESERVE DRILLING COMPANY, INC.
703 UNION NATIONAL BANK BUILDING
WICHITA, KANSAS

15.185.13255.0000

NADEL AND GUSSMAN

Fischer C #1

NWc NE/4 36-21-13W
Stafford County, Kansas

Commenced 10-19-48
Completed 10-31-48

Casing:
8" 320'
225 sax cement
5" 3634'
100 sax cement

<u>Formation</u>	<u>Depth</u>
Sand	127
Sand and shale	339
Shale and shells	1590
Broken lime	1955
Shale and lime	2330
Shale and shells	2830
Shale, shells and lime	2900
Lime	3150
Lime and shale	3311
Lime	3585
Shale	3610
Lime	3634
Lime	3636 T.D.

TOPS

Top Lansing	3300
Top Viola	3551
Top Simpson	3588
Top Arbuckle	3634

State of Kansas)
County of Sedgwick)

I hereby certify that the above formations and depths are true and correct as taken from the daily drilling report covering the Fischer C #1 well in the NWc NE/4 of 36-21-13W, Stafford County, Kansas.

L.C. Hay

Subscribed and sworn to before me this 3rd day of November, 1948.

Notary Public
OCT 22 1987

My commission expires Nov. 3, 1948

15-185.13255.0000

RESERVE DRILLING COMPANY, INC.

703 UNION NATIONAL BANK BUILDING
WICHITA, KANSAS

NADEL AND GUSSMAN

Fischer C #1

NWc NE/4 36-21-13W
Stafford County, Kansas

Commenced 10-19-48

Completed 10-31-48

Casing:

8" 320'
225 sax cement
5" 3634'
100 sax cement

<u>Formation</u>	<u>Depth</u>
Sand	127
Sand and shale	339
Shale and shells	1590
Broken lime	1955
Shale and lime	2330
Shale and shells	2830
Shale, shells and lime	2900
Lime	3150
Lime and shale	3311
Lime	3585
Shale	3610
Lime	3634
Lime	3636 T.D.

TOPS

Top Lansing	3300
Top Viola	3551
Top Simpson	3588
Top Arbuckle	3634

State of Kansas }
County of Sedgwick }

I hereby certify that the above formations and depths are true and correct as taken from the daily drilling report covering the Fischer C #1 well in the NWc NE/4 of 36-21-13W, Stafford County, Kansas.

L.C. Hay

Subscribed and sworn to before me this 3rd day of November, 1948.

Notary Public
STATE Notary Public

My commission expires Nov. 3, 1948

1957 01357