

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stafford County, Sec. 36 Twp. 21 Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW

Lease Owner El Dorado Refining Company

Lease Name Fischer Well No. 1

Office Address Brown Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-17 19 52


Application for plugging filed 9-17 19 52

Application for plugging approved 9-17 19 52

Plugging commenced 9-17 19 52

Plugging completed 9-17 19 52

Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3737 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	324'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Top plug set at 35' with 20 sacks cement  
Bottom plug set at 300' with 205 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 24 1952  
9-24-52  
CONSERVATION DIVISION  
WICHITA, KANSAS

Name of Plugging Contractor Anschutz Drilling Company, Inc.  
Address 709 Union Nat'l Bk Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Leon L. Mehler (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leon L. Mehler  
709 Union Nat'l Bk Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of September, 19 52

My commission expires May 2, 1956  
Jacqueline Korman Notary Public.

PLUGGING  
FILE SEC 36 T 21 R 13  
BOOK PAGE 25 LINE 21

DRILLER'S LOG

El Dorado Refining Company  
 #1 Fischer  
 SW SW SW - 36-21S-13W  
 Stafford County, Kansas

FROM	TO	
0	265	Sand
265	330	Red rock
330	700	Red bed & shale
700	730	Anhydrite
730	1180	Shale & shells
1180	1220	Shale, shells & salt
1220	1549	Shale & shells
1549	1700	Lime
1700	1760	Shale
1760	2385	Lime
2385	2540	Shale
2540	2740	Shale & lime streaks
2740	2900	Lime & shale
2900	3195	Lime
3195	3285	Sandy lime & shale
3285	3345	Shale & lime
3345	3590	Lime
3590	3737	Conglomerate
	3737	DF TOTAL DEPTH
		D&A

COMMENCED: 9-6-52  
 COMPLETED: 9-17-52

CASING RECORD

Set 8-5/8" surface casing at  
 324 feet with 225 sacks  
 cement.

ELEVATION: 1878 DF

TOPS

Anhydrite 700  
 Heebner 3183  
 Toronto 3203  
 Brown Lime 3313  
 Lansing 3332  
 Conglomerate 3577

DRILL STEM TEST

3412-18, open 1 hour, recovered  
 25 feet mud, weak blow 11 minutes,  
 BHP 730#.

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

I hereby affirm that the foregoing is a true and correct copy of the  
 log of El Dorado Refining Company's #1 Fischer located SW SW SW 36-21S-13W,  
 Stafford County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

BY: *Leon L. Mehler*  
 Leon L. Mehler

Subscribed and sworn to before me this 23rd day of September, 1952.

*Jequeline Korman*  
 Notary Public

My commission expires: May 2, 1956.

**PLUGGING**  
 FILE SEC 36 T 21 R 13 W  
 BOOK PAGE 45 LINE 28

RECEIVED  
 NOTARY COMMISSION  
 SEP 24 1952  
 CONSERVATION DIVISION  
 Wichita, Kansas