

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Billing Building  
Wichita, Kansas

Stafford

County. Sec. 36 Twp. 21 Rge. 13 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW NE NW

Lease Owner Nadel and Gussman

Lease Name Fischer Well No. 3

Office Address Box 309, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 3-18-1952

Application for plugging filed 3-18-1952

Application for plugging approved 3-18-1952

Plugging commenced 3-18-1952

Plugging completed 3-18-1952

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough

Producing formation Depth to top Bottom Total Depth of Well 3800 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	327	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from T.D. to 330' cemented plug at 330' with 15 sacks cement. Top plug set at 35' and cemented with ten sacks.

3-26-52

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Reserve Drilling Company, Inc.

Address 703 Union National Bank Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

L. C. Hay (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Hay

703 Union National Bank Bldg. Wichita

(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 1952

Rola Bush

Notary Public.

My commission expires Nov. 3, 1952

PLUGGING  
FILE SEC 36 T 21 R 120  
BOOK PAGE 2 LINE 31

WELL LOG

Nadel and Gussman

Fischer No. 3

SW NE NW 36-21-13W  
Stafford County, Kansas

Comm. 3-7-52  
Comp. 3-18-52

Casing: 8-5/8" 327' w/300 Sax

Formations	Depth
Clay and sand	240
Red rock	275
Red bed and shells	460
Shale and shells	710
Anhydrite and shells	1390
Shale and shells	1542
Broken lime	1655
Broken lime and shale	1785
Lime and shale	1970
Shale and lime shells	2250
Lime and shale	2460
Shale, lime shells	2760
Shale and lime	3344
Lime	3572
Lime and shale	3629
Cong. lime and shale	3690
Red rock and shale	3784
Cong.	3800

Geological Tops

Heebner Shale	3178
Brown Lime	3310
Lansing-K.C.	3326
Conglomerate	3569

STATE OF KANSAS

COUNTY OF SEDGWICK

} SS:

Nola Babb, of lawful age, deposes and states that the above formations and depths are correct as shown by the daily drilling log of the Fischer No. 3 Well in the SW NE NW 36-21-13W, Stafford County, Kansas.

*Nola Babb*

Subscribed and sworn to before me this 23rd day of March, 1952.

*Latrus Becker*  
Notary Public

My commission expires Jan. 1, 1954

**PLUGGING**  
FILE SEC 36T 21R 13W  
BOOK PAGE 2 LINE 38