

15.195.01843.0001

API NUMBER 7-22-59

LEASE NAME Fischer Estate

WELL NUMBER 3

SPOT LOCATION S $\frac{1}{2}$ SW $\frac{1}{4}$

SEC. 36 TWP. 21 RGE. 13 (E) 13

COUNTY Stafford

Date Well Completed 7-22-59

Plugging Commenced 4-7-90

Plugging Completed 4-7-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS Box 723 Hays, Kansas 67601

PHONE (913) 628 6101 OPERATORS LICENSE NO. 5245

Character of Well Inj
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City (Steve Durant)

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3673

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	245	8 5/8		
	Casing	0	3671	5 $\frac{1}{2}$		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each sat. Rig up Great Guns perf. 2 holes at 735. TIH with opened ended to 3550'. Spot 50 sks. common. Pull 10 jts. 3216'. Spot 25 sks. gel TOH with tubing. Hook to casing. Pump 225 sks. 65/35 pos with 8% gel down casing. Circ. some cement to surface on 8 5/8. Pressure 500#. Shut in 300#. Pump 75 sks. pos with 8% gel down annulus 200# pressure. Shut in.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245
 Address Box 723 Hays, Kansas 67601

BJ Titan cementer

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford

(Address) Box 723 Hays, Ks. 67601

ROSEMARY SMITH
 NOTARY PUBLIC
 STATE OF KANSAS
 MY APPOINTMENT EXPIRES MAY 1, 1991

SUBSCRIBED AND SWORN TO before me this 9 day of April, 1990

Rosemary Smith
 Notary Public

My Commission expires: APR 10 1990 5-1-1991