


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
860 Bittling Building
Wichita, Kansas

Ellis County. Sec. 7 Twp. 12 Rge. 17 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW SW NW $\frac{1}{4}$
Lease Owner Glenn R. Nye
Lease Name Karlin Well No. D¹-1
Office Address Box 30, Hays, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed February 4 19 51
Application for plugging filed February 4 19 51
Application for plugging approved February 4 19 51
Plugging commenced February 4 19 51
Plugging completed February 4 19 51
Reason for abandonment of well or producing formation dry hole



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well 3722 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	139'	Cemented in

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from...feet to ...feet for each plug set.
cementers plug and one-half sack of hulls was used to bridge surface pipe at 130'. Pipe was filled with cement from that depth to surface.

RECEIVED
STATE CORPORATION COMMISSION
FEB 8 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Glenn R. Nye Drilling Company
Address Box 30, Hays, Kansas

STATE OF Kansas COUNTY OF Ellis, ss.
Glenn R. Nye (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glenn R. Nye
Box 30, Hays, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of February, 19 51.

John L. Spiess
Notary Public.

My commission expires May 9, 1953

PLUGGING
FILE SEC 7112RL70
BOOK PAGE 60 LINE 35

Company: Glenn R. Nye et al
Contractor: Glenn R. Nye Drilling Company
Commenced: January 23, 1951
Completed: February 3, 1951

Farm: Karlin #D #1
Location: SW SW NW Sec. 7-12S-17W
Ellis County, Kansas
Casing Record: 8 5/8" set at 139'

(Figures indicate bottoms)

sand	15
shale & sand	65
shale & shells	139
shale & shells	280
shale & sand	360
shale & iron streaks	530
shale & shells	685
sand	725
shale & shells	760
sand	790
shale, shells & sand	850
shale, shells & sand	900
sand Dokato	1065
shale red bed	1295
shale & red bed	1407
anhydrite	1440
shale & red bed	1530
shale - shells	1780
shale & shells	1810
salt & shale	2015
shale & shells	2120
shale & lime	2250
lime & shale	2340
lime & shale	2395
lime & shale	2490
lime & shale	2595
lime & shale	2680
lime & shale	2740
lime & shale	2855
shale & lime	3000
shale & lime	3115
shale & lime	3205
lime & shale	3263
lime & shale	3320
lime & shale	3366
lime	3403
lime	3425
lime	3490
lime	3529
lime	3570
lime	3618
	3680
shale & lime	3710
lime	3716
ar buckle	3722 T.D.

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

GLENN R. NYE DRILLING COMPANY

By Glenn R. Nye

State of Kansas)
) SS
Ellis County)

Subscribed and sworn to before me, a Notary Public, in and for said County and State this 12 day of Feb, 1951.

My Commission Expires, May 9, 1953

John L. Lewis
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
FEB 14 1951
CONSERVATION DIVISION
Wichita, Kansas