


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Ellis County. Sec. 7 Twp. 12 NW R. 17W W (E) (W)



Locate well correctly on above Section Plat

Location as "NE/CNW/SW" or footage from lines
Lease Owner **B & R Drilling, Inc.**
Lease Name **Schneidler** Well No. **1**
Office Address **Russell, Kansas**
Character of Well (completed as Oil, Gas or Dry Hole) **Dry Hole**
Date well completed **12/10/51**
Application for plugging filed **12/9/51, verbally** 19
Application for plugging approved **12/9/51, verbally** 19
Plugging commenced **12/10/51** 19
Plugging completed **12/10/51** 19
Reason for abandonment of well or producing formation **Dry Hole**

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? **Yes**
Eidon Petty

Name of Conservation Agent who supervised plugging of this well **3863**
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Run In	Pulled Out
				8 5/8	137	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugging Record

Filled hole with mud to 170'-wood plug @ 170', 15 sacks cement through 1/2" Drill pipe, filled hole to 50'-wood plug ties with wire @ 40', 1 sack of hulls and 10 sacks cement. Filled to bottom of collar

(If additional description is necessary, see BACK of this Record)
Correspondence regarding this well should be addressed to **B & R Drilling, Inc.**
Russell, Kansas
Address _____

STATE OF **KANSAS** COUNTY OF **RUSSELL**, ss.
W. A. Michaelis, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) **W. A. Michaelis, Jr.**
Russell, Kansas

SUBSCRIBED AND SWORN to before me this **12th** day of **December**, 19 **51**

My commission expires **6-17-54** _____
Notary Public.

23-3273-S 4-50-10M
DEC 14 1951
STATE CORPORATION COMMISSION
Wichita, Kansas

B & R Drilling, Inc.
Schmeidler # 1

15.051.00616.00.00

NE NW SE of Sec. 7-12-17W
Ellis County, Kansas

Total Depth: 3863'
Comm: 11/28/51
Comp: 12/10/51

Casing

8 5/8" set @ 187

Cement

130 sacks Lone Star

Formation

Depth

Clay	125
Shale	525
Sand-shale	660
Sand	770
Sand-shale	810
Sand-shale	900
Sand	1075
Sand-shale-red bed	1300
Red bed	1380
Anhydrite	1410
Shale-shells	1760
Salt-shale	1990
Shale-lime	3165
Lime	3211
Lime-shale	3455
Lime	3706
Conglomerate	3800
Chert.	3863

STATE OF KANSAS)
) ss
RUSSELL COUNTY)

I hereby certify that the above information is true and correct to the best of my knowledge.

Cora Betty

Subscribed and sworn to before me this 12th day of December, 1951.

Clara Sumner
Notary Public

My commission expires 6-17-54.

FILED
NOV 21 1951
LOCK HARTZELL