

WELL PLUGGING RECORD

FORMATION PLUGGING RECORD

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

Strike out upper line when reporting plugging of formations.

Ellis County Sec Twp Rge (E) (W)

Location as "NE1/4NW1/4SW1/4" or footage from lines Lease Owner Palmer Oil Corporation, Wichita, Kansas. Lease Name Palmer Oil Corp-Smith Estate Well No. 1 Office Address 415 Union National Bank Bldg., Wichita, Kansas. Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole Date well completed 19 Application for plugging filed 19 Application for plugging approved 19 Plugging commenced May 27, 19 50 Plugging completed June 3, 19 50 Reason for abandonment of well or producing formation Completed as dry hole

Table with 4 columns and 4 rows for section plat. Labeled 'NORTH' and 'Locate well correctly on above Section Plat'.

If a producing well is abandoned, date of last production 19 Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes.

Name of Conservation Agent who supervised plugging of this well Eldon Petty Producing formation none Depth to top Bottom Total Depth of Well 3375 Feet Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3375 feet to surface. feet for each plug set.

Hole filled with chat from 3375 to 3340; Four sacks of cement placed in hole with dump bailer forming cement plug from 3340 to 3318; Hole filled with mud from 3318 to 200 feet; Rock bridge installed from 200 feet to 190 feet; fifteen sacks of cement poured in hole forming cement plug between 190 feet to 138 feet; mudded hole with mud from 138 feet to 35 feet; rock bridge installed between 35 feet to 30 feet - ten sacks of cement poured in hole, forming cement plug to surface. Plugging complete.

RECEIVED JUL 28 1950 STATE CORPORATION COMMISSION KANSAS

(If additional description is necessary, use BACK of this sheet) Correspondence regarding this well should be addressed to Palmer Oil Corporation, Address 415 Union National Bank Bldg., Wichita, Kansas.

STATE OF Kansas COUNTY OF Sedgwick, ss. A. H. Smith (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) A. H. Smith 415 U.N.B. Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 7th day of July, 1950. Olay M. Kelling Notary Public.

My commission expires Sept. 30, 1953

PLUGGING FILE SEC 23 T 12 R 164 BOOK PAGE 8 LINE 12

WELL LOG - SMITH ESTATE #1

WELL OWNER: The Palmer Oil Corporation and
Palmer-King Oil Corporation, Inc.

Location: SW SE SE
Section 23-123-16W
Ellis County, Kansas
Elevation: 1870 D.F.

CONTRACTOR: The Palmer Oil Corporation

Commenced: 4/8/49
Completed: 4/21/49 (Rotary)
Completed: 5/9/49 (Cable Tool)
RESULTS: Dry Hole

Casing Record

8 5/8" - 679' cemented 300 sacks
5 1/2" - 3355' cemented 100 sacks

Shale & shells	0	414	
Shale, sand, shells	414	540	
Shale & sand	540	655	
Red bed	655	676	
Red bed & shale	676	1005	
Anhydrite	1005	1050	
Shale & shells	1050	1722	
Lime & shale	1722	1925	
Lime	1925	2012	
Lime & shale	2012	2100	
Lime	2100	2200	
Lime & shale	2200	2787	
Shale	2787	2798	
Lime	2798	3040	
Lime, hard	3040	3074	
Lime	3074	3180	
Lime, Cherty	3180	3289	
Lime	3289	3358	Rotary TD
Lime	3358	3375	Cable Tool TD

Formation Tops (D.F.)

Topeka	2792
Hessner	3042
Lansing	3091
Conglomerate	None
Arbuckle	3352

This is to certify that the above is a true and correct log, according to the daily drilling reports.

THE PALMER OIL CORPORATION

RECEIVED

Corporation Div.

JUL 28 1950

STATE CORPORATION
COMMISSION
KANSAS

By A. H. Smith

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

Subscribed and sworn to before me, a Notary Public in said county and state this 27th day of July, 1950.

Claf M. Kelley
Notary Public

My commission expires: 9/30/53.

PLUGGING
WELL SEC 23 12 16W
WORK PAGE 8 LINE 12