

STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit
 Mail or Deliver Report to:
 Conservation Division
 State Corporation Commission
 211 No. Broadway
 Wichita, Kansas

NORTH

Locate well correctly on above Section Plat

Ellis County, Sec. 4 Twp. 12 Rge. 16 (E) (W)
 Location as "NE/CNW/SW" or footage from lines SW SW NE
 Lease Owner Leo J. Dreiling Oil Company
 Lease Name Chrisler "A" Well No. 1
 Office Address Victoria, Kansas
 Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
 Date well completed June 8 19 62
 Application for plugging filed June 8 19 62
 Application for plugging approved June 8 19 62
 Plugging commenced June 8 19 62
 Plugging completed June 8 19 62
 Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production -0- 19
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
 Producing formation -0- Depth to top -0- Bottom -0- Total Depth of Well 3431' Feet
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	148'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rotary mud was used to fill up hole to a depth of 350' were 1st plug was set using 20 sacks cement, 2nd plug was set at 150' using 15 sacks cement, 3rd plug was set at 40' using 15 sacks cement and filling up to top of hole.

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 2 1962
 CONSERVATION DIVISION
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.
 Address Victoria, Kansas

STATE OF Kansas, COUNTY OF Ellis, ss.
I, Leo F. Dreiling a contractor (~~XXXXXXXXXXXXXXXXXXXXXXXXXXXX~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling
Victoria, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 28th day of June, 19 62

Ronald Zimmerman
 Notary Public.

My commission expires August 14, 1965



L. J. DREILING and SONS, Inc.
VICTORIA, KANSAS

WELL LOG

Company Leo J. Dreiling Oil Company
Victoria, Kansas
Farm Chrisler "A" No. 1

Sec. 4 Twp. 12 Rng. 16

Location SW SW NE

Total Depth 3431'

County Ellis County, Kansas

Comm. June 1, 1962

Comp. June 8, 1962

Elevation: D. F. 1863'

Contractor L. J. Dreiling & Sons, Inc.
Victoria, Kansas
Casing Record

G. R. 1861'

8 5/8" - - - 1148'

Cement Record
90 sacks cement

Production:
D. & A.

Figures Indicate Bottom of Formations

0 - 50	Surface Clay
50 - 118	Shale
118 - 640	Shale & Shells
640 - 846	Shale & Red Rock
846 - 1045	Shale
1045 - 1080	Anhydrite
1080 - 1126	Shale & Shells
1126 - 1815	Shale & Lime
1815 - 2020	Shale & Lime
2020 - 2205	Lime & Shale
2205 - 2403	Lime & Shale
2403 - 2690	Shale
2690 - 2860	Shale & Shells
2860 - 2965	Shale & Lime
2965 - 3060	Lime
3060 - 3130	Lime
3130 - 3145	Lime
3145 - 3238	Lime
3238 - 3390	Lime
3390 - 3431	Lime
3431	TD

RECEIVED
STATE CORPORATION COMMISSION
JUL 2 1962
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss.
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling and Sons, Inc., upon oath states that the above and foregoing is a true and correct copy of the log from the Daily Drilling Report on your Chrisler No. 1.

Leo F. Dreiling

LEO F. DREILING

Subscribed and sworn to before me this 28th day of June, 1962.

Ronald J. Zimmerman

Notary Public