

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD 15.159.06622.0000
K.A.R.-82-3-117

API NUMBER Drilled 12-29-61

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE NAME Schafer

WELL NUMBER 2

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 2 TWP. 21 RGE. 9W (E) or (W)

COUNTY Rice

Date Well Completed

Plugging Commenced 8-7-96

Plugging Completed 8-9-96

LEASE OPERATOR RAMA Operating Co., Inc.

ADDRESS P. O. Box 159 Stafford, KS 67578

PHONE (316) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filled? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3352'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	224'	none
				5 1/2	3352'	1336'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Plugged off bottom with sand to 2895' & 5 sks cement. Shot @ 2605', worked pipe. Shot @ 2015', worked pipe. Shot @ 1808', worked pipe. Shot @ 1618', worked pipe. Shot @ 1513', worked pipe. Shot @ 1336', worked pipe free. Pulled pipe to 1230', pumped 35 sks cement w/100# hulls. Pulled to 750', pumped 35 sks cement w/100# hulls. Pulled to 275', circulated 90 sks cement to surface. Pulled rest of pipe & topped w/35 sks cement. Plugging complete. 60/40 pos 4% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: RAMA Operating Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

RECEIVED
KANSAS CORPORATION COMMISSION

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 16th day of August, 19 96

CONSERVATION DIVISION
WICHITA, KS
My Commission Expires:



Form CP
Revised 05-