

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
135 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-159-06223-0000

LEASE NAME Schafer

WELL NUMBER #1

2310 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 2 TWP. 21S RGE. 9W (E) or (W)

COUNTY Rice

Date Well Completed 11-4-61

Plugging Commenced 4-27-00

Plugging Completed 5-2-00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Rama Operating Co., Inc.

ADDRESS P.O. Box 159 Stafford, Kansas 67578

PHONE (316) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Jack luthi (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, Is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3345'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	207'	None
				5-1/2"	3343'	1810'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each section.  
Plugged off bottom with sand to 2850' and 5 sks. cement. Shot pipe @2400' ad 1810'.  
Pulled up to 1150', pumped 35 sks. cement and 100# hulls, pulled up to 750', pumped  
35 sks cement and 100# hulls, pulled up to 260', pumped 110 sks. cement and circulated  
to surface. 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rama Operating Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)  
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact  
statements, and matters herein contained and the log of the above-described well as filed to  
the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED  
STATE CORPORATION COMMISSION

SUBSCRIBED AND SWORN TO before me this 5th day of May, 2000  
MAY 8 2000

CONSERVATION DIVISION  
My Wisconsin License Expires: \_\_\_\_\_

[Signature]  
Notary Public

 IRENE HERZBERG  
State of Kansas  
My Appt. Exp. Aug. 24, 2001

Form CP  
Revised 05-