

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 4 Twp. 21S Rge. (E) 12 (W)

Location as "NE/CNW%SW%" or footage from lines. SE NE NW
Lease Owner George Reed
Lease Name DE WERFF Well No. 1
Office Address 1223 Union National Bldg., Wichita
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 20, 1967
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced September 20, 19 67
Plugging completed September 20, 19 67
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes (Archie Elving)

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 3468 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface Casing	0	244	8-5/8"	9/13/67	-----
		SEP 25	1967			
		CONSERVATION DIVISION Wichita, Kansas				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy Mud from Total Depth to 235 Feet;
Hull Plug, Plug and 25 sacks Cement thru
the Drill Pipe; Mud to 40 Feet; 1/2 sack
Hulls & Plug bridged with Kelly and
10 sacks Cement to Base of Cellar;
3 sacks in Rat Hole. Job completed
at 8:45 P.M.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sage Drilling Co.
Address 500 Bitting Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Lawrence F. Gray of Sage Drilling Co. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Lawrence F. Gray
500 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 22nd day of September 19 67
Louise K. Whitted
Louise K. Whitted - Notary Public.

My commission expires November 26, 1970.

DRILLERS LOG

DE WERFF NO. 1

CASING RECORD:	COMPANY: George Reed	DESCRIPTION:
8-5/8" @ 244' w/200 sax cement	CONTRACTOR: Sage Drilling Co.	SE NE NW Sec. 4-21S-12W Stafford County, Kansas
TOTAL DEPTH: 3468'	COMMENCED: September 13, 1967	ELEVATION: 1838KB
	COMPLETED: September 20, 1967	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Sand	0	20	
Sand	20	160	
Shale	160	405	
Red Bed	405	613	
Anhydrite	613	636	
Shale & Shells	636	1670	
Shale & Lime	1670	2325	
Lime & Shale	2325	2815	
Lime	2815	2915	
Lime & Shale	2915	3015	
Shale & Lime	3015	3153	
Lime & Shale	3153	3415	
Lime	3415	3468	D&A

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

By Lawrence F. Gray
Lawrence F. Gray

Subscribed and sworn to before me this 22nd day of September, 1967.

Louise K. Whitted, Notary Public

My commission expires:
November 26, 1970.