

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,042.0000

LEASE NAME Wise

WELL NUMBER 1

SPOT LOCATION C SE NW

SEC. 4 TWP. 21RGE. 12(X) or (W)

COUNTY Stafford

Date Well Completed 7-29-84

Plugging Commenced 7-29-84

Plugging Completed 7-29-84

LEASE OPERATOR Formation Mechanics

ADDRESS 2110 Garland Wichita, KS 67203

PHONE # (316) 264-1501 OPERATORS LICENSE NO. 8904

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? B.B. Tarbutton
to be filed by

Is ACO-1 filed? operator if not, is well log attached? to released by operator

Producing formation _____ Depth to top _____ bottom _____ T.D. 3500

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Bottom Plug: @ 630' w/50 sacks 60/40 pozmix 2% gel 3% cc. thru drill pipe
Next Plug: @ 40' w/solid bridge of 1/2 sack hulls & 10 sacks cement
15 sacks cement in Rat hole
5 sacks in Water well

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.

Bill Draney (employee of operator) or

(XXXXXX) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well was filed that the same are true and correct, so help me God.
STATE CORPORATION COMMISSION

(Signature) Bill Draney

(Address) P.O. Box 823 Great Bend, KS 67530

AUG 01 1984

CONSERVATION DIVISION
SUBSCRIBED AND
Wichita, Kansas

SWORN TO before me this 31 day of July, 1984

Dorothy M. Bagde
Notary Public

My Commission expires: 4-29-86

DRILLER'S WELL LOG

DATE COMMENCED: July 24, 1984
DATE COMPLETED: July 29, 1984

Formation Mechanics
WISE #1
C. SE NW
Sec. 4, T21S, R12W
Stafford County, Ks.

ELEVATION: 1843 K.B.

0 - 623' Surface Soil, Sand, Shale
623 - 644' Anhydrite
644 - 2812' Shale
2812 - 3036' Lime
3036 - 3040' Shale
3040 - 3053' Lime & Shale
3053 - 3069' Lime
3069 - 3163' Shale
3163 - 3179' Lime & Shale
3179 - 3396' Lime
3396 - 3411' Shale & Lime
3411 - 3500' Dolomite
3500' RTD

FORMATION DATA

Anhydrite 623'
Topeka 2812'
Heebner 3036'
Toronto 3053'
Douglas 3069'
Br. Lime 3163'
Lansing K.C. 3179'
Base K.C. 3396'
Arbuckle 3411'
RTD 3500'

Surface Pipe: Set used
8-5/8", 28# @281' w/215
sacks 60/40 pozmix 2% gel
3% cc.

A F F I D A V I T

STATE OF KANSAS
COUNTY OF BARTON) ss.

Bill Draney of lawful age, does swear and state that the facts and statements
herein are true and correct to the best of his knowledge.

Bill Draney

Subscribed and sworn to before me this 31 day of July 1984.

My Comm. Expires:

4-29-86

Dorothy M. Dague
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

AUG 01 1984

CONSERVATION DIVISION
Wichita, Kansas