

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-185-22,071-0000

LEASE NAME Spacil

WELL NUMBER 4-1R

SPOT LOCATION NW SW NE

SEC. 4 TWP. 21S RGE. 12 (KXXX(W))

COUNTY Stafford

Date Well Completed 9-24-84

Plugging Commenced 9-24-84

Plugging Completed 9-24-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Double R Oil Company

ADDRESS P. O. Box 506, McCook, NE 69001

PHONE # (308) 345-2314 OPERATORS LICENSE NO. 9800

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 3540' RTD

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		-0-	265'	8 5/8"	265'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Mud laden fluid 3540' - 3430' 10 sks cement @ Rathole
40 sks cement @ 3430' 10 sks cement @ Mousehole
50 sks cement @ 630'
60 sks cement @ 300'
10 sks cement @ 40'

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750

Address P. O. Box 506, Russell, KS 67665

STATE OF KANSAS COUNTY OF RUSSELL, ss. RECEIVED
STATE CORPORATION COMMISSION

Joe K. Branum (employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

DENISE S. REYNOLDS
NOTARY PUBLIC
STATE OF KANSAS
My Appointment Expires:
2-13-85

(Signature) Joe K. Branum
 (Address) P. O. Box 506
Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 25th day of September, 19 84

My Commission expires: February 13, 1985

Denise S. Reynolds
Denise S. Reynolds, Notary Public

EMPHASIS OIL OPERATIONS

P. O. BOX 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Double R Oil Company
P. O. Box 506
McCook, NE 69001

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, KS 67665

LEASE: Spacil WELL: #4-1R

LOCATION: NW SW NE
Section 4-21S-12W
Stafford County, Kansas

ROTARY TOTAL DEPTH: 3540'

LOG TOTAL DEPTH: 3542'

ELEVATION: 1838' K.B.

COMMENCED: 9-17-84

DATE COMPLETED: 9-24-84

CASING: 8 5/8" @ 265' with 200 sks cement

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Sand	30'	Shale	2305'
Sand & Shale	616'	Shale & Lime	2925'
Anhydrite	640'	Lime & Shale	3443'
Sand & Shale	1320'	Lime (RTD)	3540'
Shale & Shells	1850'		

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

Joe K. Branum

Joe K. Branum


RECEIVED
STATE CORPORATION COMMISSION

Subscribed and sworn to before me this 25th day of September, 1984.

SFP 26 1984

My Commission Expires: February 13, 1985.

CONSERVATION DIVISION
Wichita, Kansas



Denise S. Reynolds

Denise S. Reynolds, Notary Public