


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800-Sitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Stafford County, Sec. 4 Twp. 21 Rge. 12 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines NE NW NE  
Lease Owner S. A. Yarnell et al Operator  
Lease Name Spacil Well No. 4  
Office Address 1009 E. Douglas Wichita 7, Kansas.  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed April 28 1950  
Application for plugging filed August 18 1953  
Application for plugging approved August 19 1953  
Plugging commenced August 31 1953  
Plugging completed September 5 1953  
Reason for abandonment of well or producing formation production exhausted

If a producing well is abandoned, date of last production June 1953  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Meril Rives  
Producing formation Arbuckle Depth to top 3420 Bottom 3426 Total Depth of Well 3426 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	275	None
				5 1/2"	3423	2945' 10"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

3426 to 3410 Filled with sand  
3410 to 3380 5 sacks cement  
3380 to 250 Mudded  
250 to 240 Rock bridge  
240 to 215 20 sacks cement  
215 to 30 Mud  
30 to cellar 10 sacks cement

9-16-1953

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor R & S Pipe Pulling Co. License #1  
Address Ellinwood, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
S. A. Yarnell (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. A. Yarnell  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN to before me this 15th day of September, 1953

My commission expires Sept 15, 1954  
Notary Public.

PLUGGING  
FILE SEC 4 T 21 R 12W  
BOOK PAGE 122 LINE 27

S. A. YARNELL  
1009 East Douglas  
WICHITA 7, KANSAS

15.185.12834.0000

WELL LOG

S.A. YARNELL Operator

Elevation 1838'

Contractor Quaker Drilling Company, Inc.

Commenced 4-13-50

Completed 4-28-50.

Spacil No. 4

NE NW NE Sec 4-21S-12W

Stafford County

Casing record Set 275' of 8 5/8" with 225 sacks of cement

=====

Figures indicate Bottom of Formations)

Formation	Depth	Formation Tops	
Surface clay and sand	205	Heebner	3032 -1192
Shale and shells	275	Brown Lime	3162 -1322
Shale and Red Bed	615	White Lime	3178 -1338
Anhydrite	640	Conglomerate	3400 -1560
Shale and shells	795	Simpson shale	3414 -1574
Shale	1285	Simpson sandstone	3417 -1577
Shale and lime	1635	Arbuckle	3420 -1580
Lime	1795	Set 5 1/2" Casing	3423 -1583
Lime and shale	2835	T.D. Rotary	3426 -1586
Lime	2910		
Lime and shale	3420		
Dolomite	3423		

**PLUGGING**  
FILE SEC 4 T 21 R 12W  
BOOK PAGE 122 LINE 27

RECEIVED  
APR 29 1950  
CANCELLER