


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bixling Building
Wichita, Kansas

Stafford County, Sec. 4 Twp. 21 Rge. 12 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NW NW NE
Lease Owner S. A. Yarnell et al
Lease Name Spacil Well No. 5
Office Address 1009 E. Douglas Wichita 7, Kansas.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed April 30 1950
Application for plugging filed August 18 1953
Application for plugging approved " 19 1953
Plugging commenced August 23 1953
Plugging completed " 30 1953
Reason for abandonment of well or producing formation production exhausted



Locate well correctly on above
Section Plot

If a producing well is abandoned, date of last production June 1953
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Meril Rives
Producing formation Arbuckle Depth to top 3404 Bottom 3409 Total Depth of Well 3409 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	275	none
				5 1/2"	3423	2815

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3421 to 3400	Sand bridge
3400 to 3370	5 sacks cement
3370 to 250	Mudded
250 to 240	Rock bridge
240 to 220	20 sacks cement
220 to 30	Mud
30 to cellar	10 sacks cement

STATE OF KANSAS

9-15-1953

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R. & S. Pipe Pulling Co. License #118580
Address Box 192 Ellinwood, Kansas.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
S. A. YARNELL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. A. Yarnell
1009 E. Douglas, Wichita 7, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of September, 1953

My commission expires Sept 15, 1954
Notary Public.

PLUGGING
FILE SEC 4 T 21 R 12W
BOOK PAGE 122 LINE 26

S. A. YARNELL

15.185.13030.0000

1009 East Douglas
WICHITA 7, KANSAS

WELL LOG

S. A. Yarnell Operator

Elevation 1839 R. B.

Contractor Quaker Drilling Co. Inc.

Commenced 4-22-50

Completed 4-31-50

Spacil No. 5

NW NW NE Sec. 4-21S-12W

Stafford County, Kansas

Casing Record: Set 275' Of 8 5/8" with 225 Sacks Cement

(Figures indicate Bottom of Formations)

FORMATION	Depth	FORMATION TOPS		
Surface clay and sand	275	Heebner	3026	-1187
Shale and Red Bed	612	Brown Lime	3154	-1315
Auhydrite	640	Lansing	3168	-1329
Shale and Shells	920	Arbuckle	3404	-1565
Shale and Lime	1530	Set 5 1/2" @	3406	-1567
Lime	1820	T.D. Rotary	3409	-1570
Lime and Shale	3025			
Lime	3085			
Shale and Lime	3155			
Lime	3289			
Lime and Shale	3404			
Dolomite	3409			

RECORDED
STATE COMMISSION

SEP 15 1950

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
 FILE SEC 4 T 21 R 12W
 BOOK PAGE 122 LINE 26