


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stafford County. Sec. 4 Twp. 21S Rge. 12W (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE SW NE  
Lease Owner S. A. Yarnell & L. K. Parrish  
Lease Name Spacil Well No. 3  
Office Address 152 N. Emporia, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed Sept. 18, 1949  
Application for plugging filed Sept. 15, 1952  
Application for plugging approved Sept. 16, 1952  
Plugging commenced Sept. 18, 1952  
Plugging completed Sept. 24, 1952  
Reason for abandonment of well or producing formation Production too small  
to continue to operate  
If a producing well is abandoned, date of last production August 1952  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well  
Producing formation Arbuckle Depth to top 3438 Bottom 3459 Total Depth of Well 2459 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lime and shells			275	8 5/8"	275'	none
					225 sacks cement	
Arbuckle		3438	3459	5 1/2"	3438'	2789.02'
					60 sacks cement	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

From 3459' to 3430' - Sand  
From 3430' to 3395' - Cement (5 sacks)  
From 3395' to approximately 275' heavy mud (25sacks) - squeezed by pump truck  
Approximately 275' - Bottom of cellar- cement (75 sacks mixed and squeezed by pump truck)  
Hole squeezed with 20 sacks mud and 75 sacks of cement, mixed and squeezed by pump truck

RECEIVED  
STATE CORPORATION COMMISSION

OCT 7 1952

CONSERVATION DIVISION  
Wichita, Kansas

10-10-1952

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pulling, Inc.  
Address 629 West Broadway, Stafford, Kansas

STATE OF KANSAS, COUNTY OF Sedgwick, ss.  
S. A. Yarnell (employee or owner) or (owner & operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) S. A. Yarnell

152 N. Emporia, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 10th day of October 1952

My commission expires Sept 15, 1954

23-8390-s 6-51-20M

Notary Public

PLUGGING  
FILE SEC 4 T21 R 12  
BOOK PAGE 44 LINE 13

15.185.12833.0000

S. A. YARNELL  
152 NORTH EMPORIA  
WICHITA 2, KANSAS

WELL LOG

S. A. YARNELL & L. K. PARRISH

ELEVATION : 1840 R. B.

Contractor: QUAKER DRILLING CO. INC.

Commenced: Sept. 10, 1949

SPACIL NO. 3  
NE SW NE Sec. 4-21S-12W  
Stafford County, Kansas.

Completed: Sept. 18, 1949

Production: 268 BOPD

CASING RECORD

Set 8 5/8" to 275' with 225 sacks of cement  
Set 5 1/2" at 3438' with 60 sacks of cement

-----  
-----  
( Figures indicate bottom of formations )

Formations:	Depths	Formation Tops:		
Surface clay & sand	210	Anhydrite	618	-1222
Shale, lime and shells	275	Lansing K. C.	3185	-1345
Shale and shells	450	Arbuckle	3438	-1598
Red Bed	618	T.D. (R)	3446	-1606
Anhydrite	648	T. D. (C)	3459	-1619
Shale and shells	1635			
Lime and shale	3020			
Lime	3095			
Shale and lime	3220			
Lime	3305			
Lime and shale	3446 T.D.			

RECEIVED  
CONSERVATION COMMISSION  
OCT 10 1952  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
WELL SEC 4 T 21 S 12 W  
BOOK PAGE 44 LINE 43