


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Stafford County. Sec. 15 Twp. 21 Rge. 13 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SE NW SE
Lease Owner Don W. Jones
Lease Name Herb "A" Well No. 1
Office Address 1311 Union Nat'l Bank Bldg. Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4-10- 19 54
Application for plugging filed 5-7- 19 54
Application for plugging approved 5-9- 19 54
Plugging commenced 5-12 19 54
Plugging completed 5-12 19 54
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production ---- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3693 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		201'	8 5/8"	Surface Casing		
		3691'	5 1/2"	Oil String		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back with Crushed rock to 3615', dumped 5 sax cement at 3615 with dump bailer, top of cement 3580'. Pumped 20 sax mud & 65 sax cement by Globe Cementing Company to plug well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Company
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Charles W. Aikins, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Charles W. Aikins, Jr.*
1311 Union National Bank Building
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of May, 19 54

Leta Nelson
Notary Public.

My commission expires August 25, 1956

PLUGGING
FILE SEC 15 T 21 R 13W
BOOK PAGE 32 LINE 1

RECEIVED
CORPORATION COMMISSION
MAY 19 1954
CONSERVATION DIVISION
Wichita, Kansas

5-19-1954

HERB "A" NO. 1 WELL

LOCATION: SE/4 NW/4 SE/4 Spudded: 3-31-54
 Section 15-21S-13W
 Stafford County, Kansas Completed: 4-10-54

OPERATOR: ~~Charles W. Wilkins, Jr. and~~
 Don Jones ~~J.W. Owen~~
 1012 Daniel Bldg. ~~215 Union National Bank Building~~
 Tulsa, Oklahoma ~~Wichita, Kansas~~

CONTRACTOR: Birmingham-Bartlett Drilling Co.
 300 Kaufman Building
 Wichita 2, Kansas

SURFACE CASING: 8 5/8" 24# casing cemented at 201' with
 140 sacks cement and 2 cc.

OIL STRING: 5 1/2" casing cemented at 3691' with
 100 sacks cement

LOG

(Figures indicate bottom of formation)

0	-	65	Sand
		110	Hard sand and iron
		525	Shale and shells
		740	Red bed
		760	Anhydrite
		1400	Shale and shells
		1735	Broken lime
		1975	Lime and shale
		2540	Shale and shells
		2720	Shale
		2970	Lime and shale
		3131	Lime
		3200	Shale and lime
		3300	Shale and sand
		3306	Shale
		3325	Brown lime
		3586	Lime
		3625	Shale and sand
		3693	Lime
		3693	RTD

The undersigned, Richard Hindery, one of the partners of Birmingham-Bartlett Drilling Co., hereby certifies that the above is a true and correct log of the formations encountered in drilling the Herb "A" No. 1 Well as shown in the daily drilling reports.

BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery

Subscribed and sworn to before me
 this 12th day of April, 1954.

Beverly Larson
 Notary Public

PLUGGING
 FILE SEC 15 T 21 S 13 W
 BOOK PAGE 32 LINE 1

NOTARY PUBLIC
 STATE OF KANSAS
 My Commission Expires
 MAY 11 1954
 Wichita, Kansas

My commission expires October 2, 1954