

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Stafford County, Sec. 15 Twp. 21 Rge. 13 (#) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW SW

Lease Owner Petroleum, Inc.

Lease Name Herb Well No. 1

Office Address 100 Derby Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 8, 1952

Application for plugging filed March 8, 1952

Application for plugging approved March 8, 1952

Plugging commenced March 8, 1952

Plugging completed March 8, 1952

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Merle Rives

Producing formation Depth to top Bottom Total Depth of Well 3698 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	219'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up to 219' and set wooden plug at 219'. Cemented and displaced 15 sacks cement through drill pipe on top of plug. Mudded up to 35' and set wooden plug at 35'. Placed 10 sacks cement on top of plug filling hole to base of well cellar.

3-13-1952 3-13-1952

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company  
Address 100 Derby Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, SS.  
Charlotte Weidman (employee of owner) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charlotte Weidman  
100 Derby Bldg., Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 12th day of March, 1952

Margorie Bradshaw  
Notary Public.

My commission expires October 27, 1952

23-8390-s 6-51-20M

PLUGGING  
FILE SEC. 15 T. 21 R. 13  
PAGE 149 LINE 5

DRILLER'S LOG HERB NO. 1

Petroleum, Inc. et al, Lease Owners	Section 15, Twp. 21S, Rge. 13W
Garvey Drilling Co., Contractor	Location: NW NW SW
Drilling Commenced: February 26, 1952	County: Stafford, Kansas
Drilling Completed: March 8, 1952	Production: D & A
Casing Record: 8 5/8" O 219' w/175 sax	R.T.D.: 3698

Figures below indicate bottom of formation:

65 Sandy soil  
 120 Hard Sand  
 320 Shale & Shells  
 400 Red Bed  
 747 Red Bed, Shale & Shells  
 768 Anhydrite  
 1475 Shale & Shells  
 1740 Brown Lime  
 1750 Brown Lime & Shale  
 1860 Sandy Lime  
 2310 Shale & Lime  
 2835 Shale & Shells  
 2975 Shale & Lime  
 3048 Brown Lime & Shale  
 3217 Lime & Shale  
 3255 Shale & Shells  
 3329 Shale & Lime  
 3385 Lime  
 3446 Shale & Lime  
 3513 Lime  
 3580 Lime & Shale  
 3597 Lime  
 3629 Shale & Lime  
 3640 Sand & Shale  
 3653 Shale & Lime  
 3698 Lime

Tops:

Heebner: 3181 (-1288)  
 Brown Lime: 3307 (-1414)  
 Lansing: 3320 (-1427)  
 Simpson: 3593 (-1700)  
 Arbuckle: 3648 (-1755)

I hereby certify that this is a true and correct log of the above mentioned well.

STATE OF KANSAS )  
 )  
 COUNTY OF SEDGWICK )

SS:

PETROLEUM, INC.  
 DRUGGING  
 FILED MAR 15 2 10 13 W  
 BY  
 PAGE 49 LINE 5

*Charlotte Weisman*

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 12th day of March, 1952.

*Margorie Bradshaw*  
 Notary Public

My commission expires: October 27, 1952.