

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 15 Twp 21S Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines NE 1/4 NW 1/4 SE 1/4

Lease Owner Birmingham-Bartlett Drilling Co.

Lease Name Herb "A" Well No. 1

Office Address 300 Kaufman Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed Well put on pump on Nov. 1 19 52

Application for plugging filed June 18 19 53

Application for plugging approved June 22 19 53

Plugging commenced July 2 19 53

Plugging completed July 10 19 53

Reason for abandonment of well or producing formation Production depleted to non-commercial status

If a producing well is abandoned, date of last production May 5 19 53

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Arbuckle Depth to top 3608 Bottom 3665 Total Depth of Well 3665 Feet

Show depth and thickness of all water, oil and gas formations. Then produced from Lansing: Top Lansing 3310'

Perforated from 3390' to 3400' with 54 shots. Packer set at 3421'.
OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	218'	None
				5-1/2"	3610'	2796'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 3662 feet to surface feet for each plug set.

Chat placed in hole from bottom at 3662 feet to 3370 feet' five sacks of cement placed in hole to form cement plug from 3370 to 3330 feet after which Sun Cementing Company pumped in 70 sacks of mud, and pumped plug down to 210 feet and pumped in 70 sacks of cement to cement well from 210 feet to surface.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Barnes & Sons Casing Pulling Co.

Address Russell, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK ss.

Chas. H. Keevert, Production Superintendent of Birmingham-Bartlett Drilling Co., owner & opr well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Chas. H. Keevert

2517 17th Street, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of July, 19 53

My commission expires November 29, 1954.

Vivian L. Genger
STATE CORPORATION COMMISSION Notary Public.

JUL 21 1953

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 15 T 21 R 130
BOOK PAGE LINE

HERB NO. 1 WELL

LOCATION: NE/4 NW/4 SE/4 SPUDDED: 10- 5-52
 Section 16-21S-13W
 Stafford County, Kansas COMPLETED: 10-15-52

OPERATOR: Birmingham-Bartlett Drilling Co.

CONTRACTOR: Birmingham-Bartlett Drilling Co.

SURFACE CASING: 8 5/8" casing cemented at 217' with
 225 sacks cement and 2 cc.

OIL STRING: 5 1/2" O.D. 15.50 and 14# casing
 cemented at 3610' with 125 sacks cement

LOG

(Figures indicate bottom of formation)

0 -	60	Surface sand
	170	Hard sand
	215	Hard sand and shale
	425	Shale and shells
	445	Red rock and shale
	770	Anhydrite
	1550	Shale and shells
	1630	Lime
	2100	Broken lime
	2700	Shale and shells
	3020	Lime and shale
	3130	Lime
	3297	Lime and shale
	3302	Brown lime
	3315	Lime and shale
	3555	Lime
	3595	Shale
	3613	Shale and lime
	3613	Rotary Depth

The undersigned Richard Hindery of the Birmingham-Bartlett Drilling Co. hereby certifies that the above is a true and correct log of the formations encountered in drilling the Herb No. 1 well as shown in the daily drilling reports.


BIRMINGHAM-BARTLETT DRILLING CO.

By Richard Hindery

Subscribed and sworn before me
 this 20th day of October 1952.

Beverly Larson
 Notary Public

My commission expires October 2, 1954



RECEIVED
 REGISTRATION COMMISSION

JUL 21 1953

REGISTRATION DIVISION
 Wichita, Kansas