


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Stafford County, Sec. 15 Twp. 21 Rge. 13 ~~XX~~/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
NW-NW-SE

Lease Owner L. D. Davis  
Lease Name Herb Well No. 1  
Office Address P. O. Box 324 Great Bend, Kansas  
Character of Well (Completed as Oil, Gas or Dry Hole)  
dry hole



Date Well completed October 2, 1980  
Application for plugging filed October 2, 1980  
Application for plugging approved October 2, 1980  
Plugging commenced 12:30 A.M. October 2, 1980  
Plugging completed 1:30 A.M. October 2, 1980  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Bill Owens  
Producing formation Depth to top Bottom Total Depth of Well 3650'  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

600' with 50 sx. 50/50 Pozmix  
300' with 40 sx. " "  
40' with 10 sx. " "  
5 Sacks in rathole



(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Halliburton

STATE OF Kansas COUNTY OF Barton, ss.  
Don Popp (employee of owner) or

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Don Popp Holsington, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of October, 1980

Bessie M. DeWerff Notary Public.

My commission expires 5-20-81

BESSIE M. DEWERFF  
STATE NOTARY PUBLIC  
BARTON COUNTY, KANSAS  
MY APPT. EXP. 5-20-81

DRILLERS WELL LOG

L. D. DRILLING, INC. - CONTRACTOR L. D. DAVIS - OPERATOR

HERB # 1  
 NW NW SE  
 Sec. 15-21-13  
 Stafford County, Ks.

T.D. 3650'  
 ELEV. 1886'

COMMENCED: 9-27-80  
 COMPLETED: 10-2-80

CASING:

8-5/8" set at 265'

CEMENT:

W/280 sx. 50/50 Pozmix, 2% Gel, 3% CC

FORMATION:

Sand  
 Hard Sand  
 Red Bed  
 Anhy.  
 Shale & Shells  
 Shale W/ Shells  
 Shale W/Lime  
 Lime & Shale  
 Shale W/shells  
 Lime & Shale

DEPTH

0 - 69  
 69 - 304  
 304 - 740  
 740 - 764  
 764 - 1625  
 1625 - 2000  
 2000 - 3135  
 3135 - 3340  
 3340 - 3370  
 3370 - 3650

TOPS

Heebner	3181	(-1295)
Toronto	3199	(-1313)
Douglas	3216	(-1330)
Brown Lime	3310	(-1424)
L. K/C	3323	(-1437)
Base K/C	3541	(-1655)
Cong.	3562	(-1676)
R.T.D.	3650	(-1764)

AFFIDAVIT

STATE OF KANSAS )  
 COUNTY OF BARTON )

I certify that this is a true and correct copy of the above log to the best of my knowledge.

*Don Popp*  
 Don Popp

L. D. Drilling, Inc.

Sworn to and subscribed before me this 2nd day of October, 1980.

My appointment expires: 5-20-81

BESSIE M. DEWERFF  
 STATE NOTARY PUBLIC  
 BARTON COUNTY, KANSAS  
 MY APPT. EXP. 5-20-81

*Bessie M. DeWerff*  
 Notary Public: Bessie M. DeWerff

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT - 6 1980  
 CONSERVATION DIVISION  
 Wichita, Kansas