

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 15 TWP. 21 RGE. 13W E/W
Location as in quarters or footage from lines:
C S/2 NW NE

Locate Well
correctly on above
Section Platt.

Lease Owner L.D. Drilling, Inc.
Lease Name Hall #1 Well No. _____
Office Address Box 324 Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 2-20-82
Plugging completed 2-24-82
Reason for abandonment of well or producing formation _____

Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz
Producing formation _____ Depth to top _____ bottom T.D. 3607'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	307'	none
				4-1/2"	3604'	2804'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 3325' and ran 4 sacks cement. Shot casing @2820' and pulled a total of 69 joints of pipe. Plugged well with 5 sacks hulls, 26 sacks gel, 140 sacks 50/50 pos, 4% gel, 3% cc. Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

RECEIVED
STATE CORPORATION COMMISSION
3-4-1982
MAR 4 10 22
(Signature) R. Darrell Kelso
Box 176 Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 19 82
Wichita Kansas



Irene Hoover
Notary Public.

My Commission expires:

DRILLERS WELL LOG

L. D. DRILLING, INC. - CONTRACTOR

L. D. DAVIS - OPERATOR

HALL # 1
 C S/2 NW NE
 Sec. 15-21-13
 Stafford County, Kans.

T. D. 3607'
 ELEV. 1883 K.B.

COMMENCED: 6-3-80
 COMPLETED: 6-8-80

CASING:

CEMENT:

8-5/8" set at 307'
 4-1/2" set at 3604' (3' off Bottom)
 (shoe Jt. & Packer shoe 10.08')

W/275 sx. 50/50 Pozmix, 2% Gel, 3%CC
 W/150 sx. 50/50 Pozmix

FORMATION

DEPTH

Sand	0 - 65
Hard Sand	65 - 100
Sand & Shale	100 - 140
Red Bed & Sand	140 - 640
Shale & Shells	640 - 750
Anhy.	750 - 770
Shale	770 -1310
Shale & Shells	1310-1890
Shale	1890-2270
Shale W/Lime	2270-3140
Lime & Shale	3140-3530
Lime	3530-3607
R.T.D.	3607

TOPS

Heebner	3176 (-1293)
Toronto	3194 (-1311)
Douglas	3210 (-1327)
Brown Lime	3300 (-1417)
Lansing	3315 (-1432)
B/ KC	3528 (-1645)
Arb	3599 (-1716)
R.T.D.	3607

STATE OF KANSAS)
) ss
 COUNTY OF BARTON)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 20 1982

I certify that this is a true and correct copy of the above log
 to the best of my knowledge. WICHITA, KANSAS

L. D. DRILLING, INC.

Don Popp

 Don Popp

Sworn to and subscribed before me this 9th day of June, 1980.

My appointment expires: 5-20-81

Bessie M. DeWerff

 Bessie M. DeWerff, Notary Public

BESSIE M.
 STATE NOTARY
 BARTON COUNTY,
 MY COM. EX. 5-20-81