

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County. Sec. 15 Twp. 21S Rge. 13 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NE NE NW

Lease Owner George Reed

Lease Name Hall Well No. 1

Office Address Union National Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 6, 1965

Application for plugging filed March 6, 1965

Application for plugging approved March 6, 1965

Plugging commenced March 6, 1965

Plugging completed March 6, 1965

Reason for abandonment of well or producing formation Too low structurally

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes.

Name of Conservation Agent who supervised plugging of this well Archie V. Elving, Pratt, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3625 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	277.25'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 265'.
Set plug. Put in 25 sacks cement.
Filled hole with heavy mud to 40'.
Set plug. Filled to top with 1 sack
hulls and 10 sacks cement.

3-24-1965
RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor C-G Drilling Co.

Address 107 Rule Bldg., Wichita, Kansas


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Jay H. Galloway (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jay H. Galloway
107 Rule Bldg.
(Address)

Subscribed and sworn to before me this 8th day of March, 1965

My Commission expires May 20, 1967
Vicky Jacobs
Notary Public.



RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1965

WELL LOG

CONSERVATION DIVISION
Wichita, Kansas

OPERATOR: George Reed

WELL NAME: Hall #1 LOCATION: NE NE NW SEC 15-21S-13W

COUNTY: Stafford STATE: Kansas

WELL COMMENCED: Spuded 2/24/65 WELL COMPLETED: March 6, 1965

ELEVATION: 1881' K.B. TOTAL DEPTH: 3625'

PRODUCTION: Dry & Abandoned RIG NO: 2

CASING - 8-5/8": Set
277.25' (8 fts.) w/250 sks. Quickset. POB 12:30 P.M. 2/25/65
5-1/2": _____

All Measurements taken from the top of rotary bushing.

FROM	TO	FORMATION	DEVIATION FROM VERTICAL	REMARKS:
0	95	Sand		
95	165	Shale		
165	277	Sand & Shale		
277	730	Red Bed	500' - 1/4°	
730	765	Anhydrite		
765	1575	Shale & Shells	1000' - 1/4°	
1575	3325	Lime & Shale	1500' - 1/2°	
3325	3625	Lime	2000' - 1/2°	DST 3440'-3450'
			2500' - 1/4°	DST 3473'-3505'
			3000' - 1/4°	

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

The undersigned hereby certifies that to the best of his knowledge and belief, the above facts are true and correct.

C-G DRILLING CO.

By Jay H. Galloway
Jay H. Galloway

SUBSCRIBED AND SWORN TO, BEFORE ME, This 8th day of March, 1965.

My Comm. Exp. May 20, 1967

Vicky Jacobs
Vicky Jacobs - Notary Public

