

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Rice SEC. 2 TWP. 21 RGE. 9 E/W  
Location as in quarters or footage from lines:  
NE NE SW


Locate Well  
correctly on above  
Section Platt.

Lease Owner Petroleum Energy, Inc.  
Lease Name STEVENSON Well No. 1  
Office Address 415 First Nat'l Bk. Bldg. Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole):  
Date Well Completed 2-25-83  
Application for plugging filed 2-25-83  
Plugging commenced 2-25-83  
Plugging completed 2-25-83  
Reason for abandonment of well or producing formation \_\_\_\_\_

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Jack Haley  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3333'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out.

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_  
feet to \_\_\_\_\_ feet for each plug set.

Bottom Plug: @ 310' w/50 sacks cement thru drill pipe  
Top Plug: @ 40' w/1/2 sack hulls & 10 sacks cement  
10 sacks cement in Rat Hole

STATE CORPORATION COMMISSION  
RECEIVED  
MAR 7 1983  
CONSERVATION DIVISION  
Wichita, Kansas

3-1-1983

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Duke Drilling Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.  
Leonard Williamson (employee of owner) or (~~owner or operator~~) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson  
Box 823 Great Bend, KS 67530  
(Address)

SUBSCRIBED AND SWORN TO before me this 28 day of Feb, 1983

Clarity M. Haque  
Notary Public.

My Commission expires: 4-29-86

DRILLERS' WELL LOG

DATE COMMENCED: February 20, 1983  
 DATE COMPLETED: February 25, 1983

Petroleum Energy, Inc.  
 STEVENSON #1  
 NE NE SW  
 Sec. 2, T21S, R9W  
 Rice County, Ks.

ELEVATION: 1675 K.B.

0 - 253' Surface Soil, Clay, Sand, Red  
 Bed, Shale  
 253 - 275' Anhydrite  
 275 - 2462' Lime & Shale  
 2462 - 2496' Lime  
 2496 - 2504' Shale & Sand  
 2504 - 2754' Lime  
 2754 - 2759' Shale  
 2759 - 2771' Lime & Shale  
 2771 - 2788' Lime  
 2788 - 2890' Shale  
 2890 - 2919' Lime & Shale  
 2919 - 3223' Lime  
 3223 - 3289' Shale, Lime, Chert, Sand  
 3289 - 3325' Chert  
 3325 - 3333' Shale & Sand  
 3333' RTD

FORMATION DATA

Anhydrite	253'
Howard	2462'
Severy	2496'
Topeka	2504'
Heebner	2754'
Toronto	2771'
Douglas	2788'
Br. Lime	2890'
Kansas City	2919'
Base K.C.	3223'
Conglomerate	3254'
Viola	3289'
Simpson Shale	3325'
Simpson Sand	3329'
RTD	3333'

Surface Pipe: Set new 8-5/8", 20#  
 pipe @248' w/175 sacks 60/40 pozmix  
 2% gel 3% cc.

A F F I D A V I T

STATE OF KANSAS  
 COUNTY OF BARTON) ss:

Leonard Williamson of lawful age, does swear and state that the facts and  
 statements herein are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 28 day of February 1983.

My Comm. Expires:

4-29-86

Abigail M. Hague  
 Notary Public

RECEIVED  
 STATE DEPARTMENT COMMISSION  
 MAR 1 1983  
 CONSERVATION DIVISION  
 Wichita, Kansas