

15.159.30057.0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
NOV 2 1967
11-2-1967
CONSERVATION DIVISION
WICHITA, KANSAS

Operator's Full Name Great Bend Pipe & Supply Co., Inc.

Complete Address: Drawer "B", Great Bend, Kansas 67530

Lease Name Schafer "C" Well No. 2

Location SW SW SE Sec. 2 Twp. 21 Rge. 9 (E) (W) X

County Rice Total Depth 2949'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour Noon Day 28 Month October Year 1967

The Above well was plugged as follows:

Hole filled with sand to 2925' and cemented with 5 sacks.

Hole filled with mud to 220'. Rock bridge set from 220' to 210' and hole cemented with

20 sacks. Hole filled with mud to 40'. Rock bridge set from 40' to 30' and hole

cemented to base of cellar with 10 sacks..

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 11/3/67

INVL NO. 6619-4

W E L L L O G

Lee Phillips Oil Company
 Schafer "C" #2, SW SW SE
 Section 2-21S-9W
 Rice County, Kansas

Figures indicate bottom of formation:

ELEVATION: 1674' KB	0	to	10	cellar
			15	clay
			55	sand
PIPE RECORD:			260	red rock
8 5/8" set @ 222'			965	shale
with 185 sacks.			1300	shale & shells
5 1/2" set @ 2942'			1600	lime & shale
with 75 sacks.			1725	shale & shells
			1935	lime & shale
			2205	shale & shells
ROTARY COMMENCED: 5-18-65			2365	shale & lime
ROTARY COMPLETED: 5-24-65			2930	lime & shale
			2949	lime
			2949	Rotary Total Depth

TOPS:
 Heebner 2755
 Douglas 2790
 Brown Line 2890
 Kansas City 2921

RECEIVED
 STATE OF KANSAS
 OCT 26 1961
 CONSERVATOR GENERAL
 WICHITA, KANSAS

STATE OF KANSAS)
 COUNTY OF BARTON) ss

I, Dean Wells, Partner of Isern Drilling Company, contractor for the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matter herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

Dean Wells
 DEAN WELLS

Subscribed and sworn to before me on this 26th day of May, 1965.

George A. Meyer
 George A. Meyer, Notary Public

My commission expires: February 10, 1967.