

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed September 12, 1967.

Operator's Full Name George Reed

Complete Address: 1223 Union National Bldg., Wichita, Kansas 67202

Lease Name De Werff Well No. # 1

Location SE NE NW Sec. 4 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3468'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Sage Drilling Company, Inc.

Address: 500 Bitting Bldg., Wichita, Kansas License No.

Operation Completed: Hour 9:00PM Day 20th Month Sept. Year 1967

The Above well was plugged as follows:

244' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fluid level
in the hole was at 90'. 1st cementing plug and 1/2 sack of hulls was pushed
in fluid to 235', and cemented with 25 sacks, through the drill pipe, with
cement from 235' to 160'. Hole was filled with drilling mud to 40', 2nd
cementing plug, bridged with 1/2 sack of hulls on fluid at 40', and cemented
with 10 sacks, with cement from 30' to the base of the cellar. Rat hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

Signed: Arlene Elving
Well Plugging Supervisor

INVOICED

SEP 27 1967

DATE 9/27/67

INV. NO. 6399-W CONSERVATION DIVISION
Wichita, Kansas