

15.185.30295.0000

Form CP-3
Rev. 6-26-62

10 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
OCT 3 1966
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name L. K. Parrish & Yarnell

Complete Address: 714 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Spacil Well No. # 9

Location SE NW ^{NE} SE Sec. 4 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3450'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Pipe Pullers, Inc.

Address: BOX 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 9:15AM Day 1st Month Oct. Year 1966

The Above well was plugged as follows:

252' of 8 5/8" surface pipe, cemented with 200 sacks. 3442' of 5 1/2" long string, cemented with 125 sacks. Plug back T.D. 3410'. Top perferation 3306'
Bottom of the hole was sanded to 3300', and cemented with 5 sacks, through the drill pipe. 2514' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 240', rock bridge from 240' to 230'. 4 sacks of cement was mixed in a barrel, and put on plug at 230', through the dump bailer, and let set over-night. Next morning hole was bailed dry, and 21 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 10/3/66
INV. NO. 4041-W