

15.185.30296.0000

Form CP-3
Rev. 6-26-62

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1966
CONSERVATION DIVISION
Wichita, Kansas
10-24-66

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name L. K. Parrish

Complete Address: 714 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Hewitt Well No. # 3

Location NE SW SW Sec. 4 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3520'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Sage Drilling Company, Inc.

Address: 500 Bitting Bldg., Wichita, Kansas License No. _____

Operation Completed: Hour 8:45 AM Day 21st Month Oct. Year 1966

The Above well was plugged as follows:

251' of 8 5/8" surface pipe, cement circulated with 200 sacks. Fluid level in the hole was at 90'. 1st cementing plug and 1/2 sack of hulls was pushed in fluid to 240', and cemented with 25 sacks, through the drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug bridged with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 10/24/66

INV. NO. 4162-W