

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

SEP 21 1965

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, KansasOperator's Full Name L. K. ParrishComplete Address: 714 Fourth National Bank Bldg., Wichita, KansasLease Name Fred Hewitt Well No. # 1Location NW SW SE Sec. 4 Twp. 21 Rge. 12 (E) (W) WCounty Stafford Total Depth 3492'Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: C-G Drilling CompanyAddress: 107 Rule Bldg., Wichita, Kansas License No. Operation Completed: Hour 10:30AM Day 20th Month Sept. Year 1965

The Above well was plugged as follows:

254' of 8 5/8" surface pipe, cemented with 350 sacks. Fluid level in
the hole was at 65'. 1st cementing plug and 1 sack of hulls was pushed
in fluid to 225', and cemented with 25 sacks, through the drill pipe.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with dry cement and hulls on fluid at 40', and cemented with
10 sacks to the base of the cellar. Rat hole bridged and cemented
2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Achie Elving
Well Plugging SupervisorDATE 9/21/65
INV. NO. 1842-W