

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 87-5

LOCATION 21/2-24-24W

SEC. 15 TWP. 21 RGE. 13-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Andrew S. Michaux

Operator The Atlantic Refining Co Address Box #17 A. Bend-Kaus-

Field \_\_\_\_\_ County Stafford

Total Depth 3606 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 242ft. Circulated with cement.  
7 casing set at 3601ft. 175 sacks of cement. Plugged back  
with shot to 3595ft. Pumped 6 sacks of cement at 3595ft.  
Shot off & pulled the 7 casing - mud to 242ft. Set Rock  
Bridge & 20 sacks of cement at 242ft. mud to  
35ft. Bridge & 10 sacks of cement at the  
surface

Patterson & Son - Plugging Contractors

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 20 1951

8-20-51

Wichita, Kansas  
District Conservation Agent

Date 8-17-51

**PLUGGING**  
FILE SEC 15 T 21 R 13W  
BOOK PAGE 87 LINE 5