

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 8 1965

CONSERVATION DIVISION  
Wichita, Kansas

3-8-1965

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name George A. Reed

Complete Address: 1301 Union National Bldg., Wichita, Kansas

Lease Name Hall Well No. # 1

Location NE NE NW Sec. 15 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3625'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: C-G Drilling Company

Address: 107 Rule Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 8:30PM Day 6th Month March Year 1965

The Above well was plugged as follows:

279' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fluid  
level in the hole was at 76'. 1st cementing plug and 1/2 sack of hulls  
was pushed in fluid to 265', and cemented with 25 sacks, through the  
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged with hulls on fluid at 40', and cemented with 10 sacks  
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 3/8/65  
INV. NO. 796-W

Signed: Archie Elving  
Well Plugging Supervisor