

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15.185.19541.0001

RECEIVED
STATE CORPORATION COMMISSION
NOV 8 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Virginia Drilling Company, Inc.

Complete Address: 712 Brown Bldg., Wichita, Kansas

Lease Name Rose Well No. # 4

Location SW SE Sec. 22 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3594'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: Box 562, Great Bend, Kansas License No.

Operation Completed: Hour 12:30PM Day 28th Month Oct. Year 1965

The Above well was plugged as follows:

297' of 8 5/8" surface pipe, cement circulated. 3594' of 4 1/2" long string,
cemented with 75 sacks. Top perferation 3334'. Bottom of the hole was sanded
to 3300', and cemented with 3 sacks. 1780' of 4 1/2" long string was recovered
from the hole. Fluid was up in the hole. Bridge plug was pushed in fluid to
270', rock bridge from 270' to 260', 5 sacks of cement was mixed in barrel,
and put on plug at 260', through the dump bailer, and let set over-night.

Next morning hole was bailed down dry, and 20 sacks of cement was added to
the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and
cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/9/65
INV. NO. 2152-4