

15.185.19540.0001

Form CP-3  
Rev. 6-26-62

**KANSAS**  
**STATE CORPORATION COMMISSION**  
**CONSERVATION DIVISION AGENT'S REPORT**

**RECEIVED**  
STATE CORPORATION COMMISSION

JUN 21 1965

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Virginia Drilling Company, Inc.

Complete Address: 712 Brown Bldg., Wichita, Kansas

Lease Name Rose Well No. # 7

Location C SE SE Sec. 22 Twp. 21 Rge. 12 (E) (W) W

County Stafford Total Depth 3675'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: This hole was a wash down.

Plugging Contractor: Virginia Drilling Company, Inc.

Address: 712 Brown Bldg., Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 8:20 PM Day 19th Month June Year 1965

The Above well was plugged as follows:

281' of 8 5/8" surface pipe, cemented with 150 sacks. Fluid level in  
the hole was at 120'. 1st cementing plug and 1/2 sack of hulls was pushed  
in fluid to 260', and cemented with 25 sacks, through the drill pipe.  
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged  
solid with dry cement and hulls on fluid at 40', and cemented with 10  
sacks to the base of the cellar. Rat hole bridged and cemented with  
2 sacks.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
Well Plugging Supervisor

DATE 6/22/65

INV. NO. 1336-W