

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1963

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

3-15-1963

Operator's Full Name Alpine Oil & Royalty Co., Inc.

Complete Address: 800 Bitting Bldg. Wichita, Kansas.

Lease Name Bennett #1 Well No. #1

Location NW-SW-NE Sec. 11 Twp. 21 Rge. 13 (E) (W) X

County Stafford Total Depth 3567'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glenn & Smith Pipe Pulling Co.

Address: 204 E. 6th Ellinwood, Kansas License No.

Operation Completed: Hour 5PM Day 11 Month March Year 1963

The Above well was plugged as follows:

~~3567' of 5 1/2" long string plugged back to 3367'. Top perforation at
3270' Sanded to 3260' & 4 sacks cement. 2817' of 5 1/2" pipe pulled.
255' of 8 5/8" surface pipe circulated with cement. Hole filled to 200'
with mud, 10' rock bridge & 20 sacks cement. Hole filled to 40' with
mud, 10' rock bridge & 10 sacks cement to base of cellar.~~

I hereby certify that the above well was plugged as herein stated.

DATE 3/15/63

Signed: [Signature]
Well Plugging Supervisor

INV. NO. 6921-W