



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 99-7

LOCATION SW-7W-SE

SEC. 11 TWP. 21 RGE. 13-W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1-B Lease Alphie

Operator Wentz - Aronland Oil Co Address 1022 - N. B. Bldg - Wichita - Kans

Field \_\_\_\_\_ County Stafford

Total Depth 3570 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 7/8 - 282 ft - Circulated with cement.  
5 1/2 casing set at 3566 ft - Filled back from bottom  
to 3540 ft with chat - Mixed 5 sacks of cement  
at 3540 ft - Shot off & Pulled the 5 1/2 casing - Filled  
with mud to 280 ft - Back Bridged & 15 sacks of cement  
at 280 ft - Mud to 30 ft - Plug & 10 sacks of cement  
at the surface

Bill Moegele  
Plugging - Contractor

8-1-1949  
C. H. Stouck -  
District Conservation Agent

Date 7-27-49

**PLUGGING**  
FILE SEC 11 T 21 R 13W  
BOOK PAGE 99 LINE 7