

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 61-77

LOCATION CS¹/₄ - S¹/₄ - SE¹/₄

SEC. 11 TWP. 11 RGE. 13-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Mc Donald

Operator Westgate-Hereward Oil Co. Address #1009 Central Bldg. Wichita-Kans.

Field _____ County Stafford

Total Depth 2588 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 10 3/4 - 2588 ft. Circulated with cement.
7" casing set at 3546 ft. Cemented with 7.5 sacks of
Cement - Plugged back to 3548 ft with chat -
Ripped off & pulled the 7" casing after dumping
6 sacks of cement at 3540 ft - Filled hole with mud to
250 ft - Set Rock Bridge & 8 sacks of cement at 250 ft
Mud to 30 ft - Bridge & 6 sacks of cement at the surface -
Bill Morgan - Plugging Contractor*

RECEIVED
STATE CORPORATION COMMISSION

MAR 19 1951 3-19-51

CONSERVATION DIVISION

C. W. Stover
District Conservation Agent

Date 3-16-51

PLUGGING
FILE SEC 11 T 11 R 13W
BOOK PAGE 61 LINE 37