

15.185.12028.0001

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1963

CONSERVATION DIVISION
Wichita, Kansas

6-12-63

Operator's Full Name A. L. Abercrombie Inc.

Complete Address: 801 Union Center, Wichita, Kansas

Lease Name Sipes Well No. # 1

Location SW ^{SW} NW NW Sec. 11 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3582

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 10:00AM Day 11th Month June Year 1963

The Above well was plugged as follows:

274' of 8 5/8" surface pipe, cement circulated, 3582' of 5 1/2" long string,
cemented with 100 sacks. Plugged back to 3518'. Top perforation 3303'.
Sanded to 3290', cemented with 5 sacks. Fluid level was up in hole. XOX
Plug was set at 240', 10' rock bridge.
6 sacks cement was mixed and put on plug through dump bailer and let set
over night. Next morning hole bailed down and 14 sacks was added to plug.
Hole was mudded to 40', 10' rock bridge, cemented with 10 sacks to base
cellar.

2970' of 5 1/2" long string recovered from hole

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/12/63

INV. NO. 7250 W

Signed: Archie Elving
Well Plugging Supervisor