

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 88-29

LOCATION SE. SE-SW

SEC. 36 TWP. 21 RGE. 13-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Fischer Estate

Operator Pickell Drilling Co. Inc. Address 715 Fourth Natl Bank Bldg - Wichita

Field _____ County Stafford

Total Depth 3719 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe - 8 5/8 - 290 ft. Circulated with cement. 5 1/2" casing to 3687 ft. Plugged back from bottom to 3687 ft with chat - 5 sacks of cement dumped at 3680 ft. Shot off & pulled the 5 1/2" casing - Filled with mud to 290 ft. Set back Bridger & 15 sacks of cement at 290 ft - Mud to 30 ft. Plug & 10 sacks of cement at the surface. J. L. Forbes - Plugging - Contractor

RECEIVED

Conservation-Div. 4-2-1949

C. D. Stovall -
District Conservation Agent

Date 4 - 22 - 49

PLUGGING
STATE CORPORATION COMMISSION
FILE NO. 88-29
BOOK PAGE 11-12